

15-095-00499-000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Whitney Operating Co.

Complete Address: 902 1st National Bldg., Tulsa, Oklahoma

Lease Name Bryant Well No. # 1

Location SE SW Sec. 36 Twp. 28 Rge. 8 (E) (W) W

County Kingman Total Depth 4531

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drilling Co.

Address: 617 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour 5:00PM Day 25th Month Oct. Year 1963

The Above well was plugged as follows:

272' of 8 5/8" surface pipe, cemented with 250 sacks. Hole was filled
with drilling mud to 265', 1st cementing plug, bridged with 1/2 sack hulls,
cemented with 25 sacks. Hole was filled with drilling mud to 40', 2nd
cementing plug, bridged with 1/2 sack hulls, cemented with 10 sacks to
base cellar. Rat hole bridged and cemented with 2 sacks. Mouse hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/29/63

INV. NO. 1993-W

Signed: Audie Elving
Well Plugging Supervisor