

YB KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1962
10-22-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Jones-Gebert Oil Inc.

Complete Address: 1007 Central Bldg., Wichita Kansas.

Lease Name Covington #1 Well No. #1

Location C-SW-SE Sec. 27 Twp. 28 Rge. 8 (E) (W) X

County Kingman Total Depth 4540'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Jones-Gebert Oil Inc.

Address: 1007 Central Bldg., Wichita, Kansas. License No.

Operation Completed: Hour 5 PM Day 18 Month Oct. Year 1962

The Above well was plugged as follows:

221' of 8 5/8" surface pipe circulated with cement. Hole filled to 160'
with heavy drill mud, 1/4 sack hulls, 1st cementing plug and 20 sacks
cement. Hole filled to 35' with heavy drill mud, 1/4 sack hulls, 2nd cementing
plug and 10 sacks cement to base of cellar. Rathole bridged and 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/24/62

INV. NO. 5890-W

Signed: Harmon Justice
Well Plugging Supervisor