

D. R. Lauck Oil Company, Inc.  
and  
Sunray DX Oil Company

Asher #1

SW SW SW Sec. 13-24S-14W  
Stafford County, Kansas

9-24-62

Commenced: September 10, 1962

Completed: September 20, 1962

Casing Record: 201' 8-5/8" Cemented with 180 sacks Cement,  
4 sacks Calcium Chloride.

Elevation: GR 1924; DF 1926; KB 1928.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 21 1962  
CONSERVATION DIVISION  
Wichita, Kansas

## Drillers Log

## Tops

Sand	110		Sample	Wellex
Shale	160	Heebner	3451-1523	3453-1525
Shale & Red Bed	201	Toronto	3469-1541	3472-1544
Red Bed & Clay	270	Douglas	3489-1561	3491-1563
Sand & Clay	320	Brown Limestone	3590-1662	3592-1664
Red Bed	410	Lansing	3612-1684	3614-1686
Sand	440	Base Kansas City	3862-1934	3864-1936
Red Bed	750	Mississippi Chert	3968-2040	3968-2040
Sand	780	Kinderhook Shale	3972-2044	3973-2045
Red Bed	810	Total Depth	4000-2072	4001-2073
Anhydrite	835			
Shale & Shells	1400			
Shale, Shells & Red Bed	1750	DST #1 (H), 3655-3695, open 1 hour w/fair		
Anhydrite & Shells	1845	blow. Recovered 145 feet drilling		
Lime	1945	mud.		
Lime & Shale	2195		ISIP 1158#/45 min.	
Shale & Lime	2680		FSIP 1122#/60 min.	
Lime & Shale	2910		IFP 53#	
Shale & Broken Lime	3040		FFP 108#	
Lime & Shale	3100			
Lime	3455	DST #2 (H), 3730-3806, (hook wall packer)		
Heebner	3457	open 1 hour w/very weak blow.		
Limes	3489	Recovered 20 feet drilling mud		
Douglas	3590	with rainbow show of oil.		
Brown Lime	3618		ISIP 1070#/45 min.	
Lansing	3625		FSIP 785#/60 min.	
Lime	3900		IFP 10#	
Lime & Shale	3965		FFP 20#	
Lime & Chert	4000 RTD			

D&amp;A