

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- McKINNEY #1-34
Located: C SE SE, Section 34-24S-17W, Edwards County,
Kansas

OWNER: F. C. Holl, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 13, 1979
COMPLETED: July 20, 1979

TOTAL DEPTH: 4552'

LOG

0 - 166 Clay and Sand
166 - 307 Shale
307 - 810 Shale, Sand and Red Bed
810 - 1117 Red Beds
1117 - 1165 Anhydrite
1165 - 1830 Shale
1830 - 3880 Lime and Shale
3880 - 4200 Lime and Chert and Shale
4200 - 4335 Lime and Shale
4335 - 4451 Lime, Shale, Chert
4451 - 4552 Chert, Lime and Shale

CASING RECORD

Ran 7 joints used 28#, 8 5/8" casing,
292.01' set at 304' K.B. with 250
sacks 60/40 Pozmix with 3% cc. Plug
down at 7:00 PM, by Howco, 7-13-79.

Ran 107 joints new 10.5#, 4 1/2" casing,
4537.40' set at 4548' K.B. with 50 sacks
Howco Light and 100 sacks 50/50 Pozmix
with 18% salt and 5# gilsonite, 1/8#
flocele, 1/8# tuffiber and 3/4% CFR-2
per sack. 250 gal. mud flush and 20
bbl. salt flush ahead of cement. Plug
down at 10:30 PM, 7-20-79, by Howco.

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1985
6-18-85
CONSERVATION DIVISION
Wichita, Kansas