



State Corporation Commission

CONSERVATION DIVISION
 RECEIVED
 (Oil, Gas and Water) CORPORATION COMMISSION
 500 Insurance Bldg. 212 N. MAIN ST.
 WICHITA, KANSAS 67202
 AUG 31 1970
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

8-31-70

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Crandall of Thunderbird Drlg. has this
 date requested permission to plug the following described well:

Mr. Crandall guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling Co

Complete Address: Box 18412, Wichita, Kansas

Lease Name: Stocker Well No. 1

Location: NE NE Sec. 4 Twp. 24 Rge. 22 (E) (W)

County: Hodgeman Total Depth 4600 Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crandall was instructed to plug the well as follows:

8 5/8" to 450' circulated w/ cement. 5 1/2" to 4591' cemented.


Top perforations 4104' Plug bottom w/ sand & 5 sacks cement.

Top of cement 3950' Mud 3950' to 450'

Spot 35 sacks cement 450' to 350' Mud 350' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


 Conservation Division Agent