

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

22 September 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Albert Unruh of Kelso Casing Pulling has this date requested permission to plug the following described well:

Operator's Full Name: Imperial Oil

Complete Address: 720 Fourth Financial Center, Wichita, Kansas 67202

Lease Name: Wiltgen Well No. 2-31

Location: SW NE NE Sec. 31 Twp. 24 Rge. 17W (E) (W)

County: Edwards Total Depth: 4530

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Unruh was instructed to plug the well as follows:

There is 598' of 8 1/2" surface casing cement circulated with 325 lbs of cement. There is 4529' of 4 1/2" production pipe cemented with 196 lbs of cement. Perforations 4457' to 4464'. 1st plug squeezed bottom with 1 lbs of hulls & 35 lbs cement pumped plug to 4000'. 2nd plug at 600' with 4 lbs hulls 10 lbs jell & 50 lbs cement 3rd plug 7 lbs jell release rubber plug at 350' with 35 lbs and 8 lbs jell. 4th plug 40'-0' with 15 lbs cement they recovered 2770' of 4 1/2" pipe. Plugging accomplished by sun cement out of Great Bend, Kansas.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1981

CONSERVATION DIVISION
Wichita, Kansas

Paul Luthi
Conservation Division Agent