

*R* KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1966  
12-14-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Waters Well No. # 1

Location NE NE NW Sec. 33 Twp. 24 Rge. 14 (E) (W)W

County Stafford Total Depth 4261'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 3:00PM Day 12th Month Dec. Year 1966

The Above well was plugged as follows:

252' of 8 5/8" surface pipe, cemented with 225 sacks. 3976' of 5 1/2" long string, cemented with 225 sacks. Plug back T.D. 3975'. Top perforation 3836'. Bottom of the hole was sanded to 3800', and cemented with 5 sacks, through the dump bailer. 2450' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 240', bridge plug and rock bridge from 240' to 230'. 10 sacks of cement was mixed in a barrel, and put on plug at 230', through the dump bailer, and let set over-week end. Hole was bailed dry, and 15 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 12/14/66

INV. NO. 4457-W