

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 13, 1967.

Operator's Full Name Misco Supply Company

Complete Address 200 Misco Bldg., Wichita, Kansas 67202

Lease Name J. W. Jenkins Well No. # 1

Location C SW SW NE Sec. 27 Twp. 24 Rge. 12 (E) (W) W

County Stafford Total Depth 4072'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Comstock Pipe Pulling, Inc.

Address Stafford, Kansas License No. 490

Operation Completed: Hour 3:00 P.M. Day 8th Month August Year 1967

The above well was plugged as follows:

675' of 8 5/8" surface pipe, cement circulated. 3924' of 5 1/2" long string,
no record of cement. This is an open hole. Plug was pushed to 3850', sand
from 3850' to 3800', and cemented with 5 sacks, with cement from 3800' to
3760'. 1798' of 5 1/2" long string was recovered from the hole. Hole was filled
with mud to 360'; rock bridge from 360' to 350', and hole was filled with
5 yards of ready-mix cement, with cement from 350' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/9/67

INV. NO. 6100-4

Signed: Archie Elving
Well Plugging Supervisor