

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____
LOCATION C 5/2-5/2-7W
SEC. 27 TWP. 24 RGE. 12W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 6 Lease Byers 'B'
Operator Cooperative Refinery Ass'n. Address 914 Central Bldg
Wichita Kans.
Field _____ County Stafford

Total Depth 4097 Feet.

Plugging Contractor Shamrock Drilling Co.

Plugging Contractor's License No. _____

Address 407 Rule Bldg. Wichita Kansas
(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" @ 303' c.w.c. 5 1/2" Oil string set
4097' w/ 150 cc Cem. Baker plug set 3679' w/
top Ref @ 3655' Sanded hole to 3640' dumped
5 cc Cem. Shot off and pulled 5 1/2" casing.
Mudded hole to 300' set rock bridge
run 20 cc Cem. mud to 35' rock bridge
10 cc Cem. to base of cellar

Warren E. Garner
District Conservation Agent

Date May 6, 1955

5-9-55
RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 27 T 24 R 12W
BOOK PAGE 17 LINE 28