


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 3 1 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling Co.

Complete Address Box 18412, Wichita, Kansas 67218

Lease Name Stoeker Well No. 1

Location NENE Sec. 4 Twp. 24 Rge. 22 (E) (W)

County Hodgeman Total Depth 4600'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Knight Casing Pulling Co.

Address Chase, Kansas License No. 624

Operation Completed: Hour 10:00AM Day 27 Month 8 Year 1970

The above well was plugged as follows:

8 5/8" to 450' circulated w/ cement. 5 1/2" to 4591' cemented.

Top perforations 4104' Plug bottom w/ sand & 5 sacks cement.

Top of cement. 3950' Mud 3950' to 450'

Spotted 35 sacks cement 450' to 350' Mud 350' to 45'

Plug. Hulls & 15 sacks cement 45' to 0'. Allied Pump Truck.

Pulled 2450' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Lues
Well Plugging Supervisor

INVOICED
DATE 9/1/70
INV. NO. 2461-W