

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -047-20407-0000 (of this well)

Operator's Full Name Imperial Oil Co.

Complete Address 720 4th. Financial Center, Wichita, Ks. 67202

Lease Name Cross Well No. 1-32

Location NW SW Sec. 32 Twp 24s Rge. 17 (E) (WX)

County Edwards Total Depth 4504

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176-Chase, Ks. 67524 License No. 683

Operation Completed: Hour 3 Pm. Day 22 Month 9 Year 1980

The above well was plugged as follows:

599' 8 5/8" casing w/325 sax cement. 4 1/2" casing set at 4503' w/200
sax cement. Plug back to 4488'-Preforated at 4472' to 76'-Sun mixed
& pumped 1 sax hulls-35 sax common cement in 4 1/2" casing to 3900'.
Pull 2290' casing-Sun mixed & pumped 8 sax hulls-25 sax gel-125 sax
50/50 posmix cement w/4% gel & 3% cc in 8 5/8" casing to top of
casing.

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1980

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 10-3-80

INV. NO. 3241-w