

**Proposed TO:**

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-25123-00-00

Spot: NESESWSE

Sec/Twnshp/Rge: 28-20S-21W

601 feet from S Section Line, 1405 feet from E Section Line

Lease Name: BIEBER-BELTZ

Well #: 1-28

County: NESS

Total Vertical Depth: 4440 feet

Operator License No.: 3581

Op Name: RED OAK ENERGY, INC.

Address: 7701 E KELLOGG DR STE 710  
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	1380		WITH 350 SX CMT
PROD	5.5	4434	0	WITH 145 SX CMT
SURF	8.625	220		WITH 150 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/12/2016 10:00 AM

Plug Co. License No.: 3004

Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC

Proposal Rcvd. from: DICK

Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 524-1225

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 30 SX CMT & 100# HULLS. PULL TBG TO 1450' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: SCOTT ALBERG

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 05/12/2016 1:15 PM

KCC Agent: MICHAEL MAIER

**Actual Plugging Report:**

RUN TBG TO 4378' & PUMP 30 SX CMT. PULL TBG TO 1480' & PUMP 180 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 500#.

**Perfs:**

Top	Bot	Thru	Comments
4434	4443		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENTING.

Plugged through: TBG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
MAY 17 2016  
KCC DODGE CITY

51A  
KCC WICHITA  
MAY 18 2016  
RECEIVED

Form CP-2/3

20  
5-18-16