

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-21706-00-00  
Spot: W2SWSESW Sec/Twnshp/Rge: 26-14S-28W  
330 feet from S Section Line, 1600 feet from W Section Line  
Lease Name: COBERLY Well #: 1-26  
County: GOVE Total Vertical Depth: 4350 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4337		475 SX
SURF	8.625	319		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/06/2016 9:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: GERALD WALKER Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 16 sx gel and 300 # hulls.  
DV Tool at 1955' w/300 sx cement.  
Perforations: 3951' - 3956', 4162' - 4166'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/28/2016 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4150' and pumped 16 sx gel followed by 50 sx cement w/300 # hulls. Pulled tubing to 2000' and pumped 220 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 60 sx cement. Cement fell 250'.  
Tied on to backside and squeezed with 10 sx cement. Shut in pressure 300 psi.  
04/28/2016- Topped off casing with 25 sx cement. Hole standing full.

GPS: 38.80127 -100.40495

Perfs:

Top	Bot	Thru	Comments
4162	4166		
3951	3956		

Remarks: BASIC CEMENT TICKET # 1718-13244

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*(Signature)*  
\_\_\_\_\_  
(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

MAY 06 2016

MAY 13 2016

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*220*  
*5-18-16*