

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-21411-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 30-9S-23W
990 feet from N Section Line, 1650 feet from E Section Line
Lease Name: GANO Well #: 1
County: GRAHAM Total Vertical Depth: 3855 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3855		150 sx
SURF	8.625	276		200 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/26/2016 9:30 AM
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING-NELSON OIL CO. Phone: (785) 623-3290

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2016 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Junk in the hole at 1300'. Casing collapsed and could not make any hole. Ran tubing to 1300' and pumped 100 sx cement. Cement circulated to pit. POOH. Hooked to casing and pumped 20 sx cement at 250 psi. Hooked to baraden head and pumped 50 sx cement at 100 psi. Filled casing back to surface. Casing stayed full.


GPS: 39.24535 -099.92790

Remarks: GLOBEL CEMENTING TICKET # 2627

Plugged through: TBG

District: 04

Signed



Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

MAY 13 2016

CONSERVATION DIVISION
WICHITA, KS

MAY 06 2016

Form CP-2/3

no 5-18-16