

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-20703-00-01  
Spot: SWSESW Sec/Twnshp/Rge: 2-23S-22W  
332 feet from S Section Line, 3576 feet from E Section Line  
Lease Name: HOUSMAN Well #: 1  
County: HODGEMAN Total Vertical Depth: 4461 feet

Operator License No.: 9860  
Op Name: CASTLE RESOURCES, INC.  
Address: BOX 87  
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1349		WITH 200 SX CMT
PROD	4.5	4451	0	WITH 400 SX CMT
SURF	8.625	375		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2016 10:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: MIKE FRITZLER Company: FRITZLER TRUCKING Phone: (785) 625-5155

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP 30 SX CMT & 100# HULLS. PULL TO 1350' & CIRCULATE TO SURFACE. TIE ON TO ANNULUS & PUMP CMT UNTIL IT PRESSURES UP.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE  
Date/Time Plugging Completed: 05/06/2016 1:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

RUN TBG TO 4284' & PUMP 30 SX CMT & 200# HULLS. WATER CIRCULATED TO PIT. PULL TO 1354' & PUMP CMT TO SURFACE WITH 90 SX CMT. POOH & TIED ON TO BACKSIDE & PUMPED 5 SX CMT. HELD PRESSURE TO 300 PSI. TOPPED OFF 4 1/2" CASING WITH 5 SX CMT. STANDING FULL.

Perfs:

Top	Bot	Thru	Comments
4222	4230		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
MAY - 9 2016  
KCC DODGE CITY

Form CP-2/3

720  
5-18-16