

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-20764-00-00
Spot: NESESW Sec/Twnshp/Rge: 2-23S-22W
1051 feet from S Section Line, 2954 feet from E Section Line
Lease Name: HOUSMAN Well #: 2
County: HODGEMAN Total Vertical Depth: 4460 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4455		
PROD	4.5	4460	1452	WITH 225 SX CMT
SURF	8.625	1164		WITH 425 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/03/2016 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE FRITZLER Company: FRITZLER TRUCKING Phone: (785) 798-3641

Proposed Plugging Method: PLUG AT 1350' WITH 12 SX GEL & 60 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/03/2016 11:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

BRIDGE PLUG AT 4455'. SQUEEZED CASING LEAKS FROM 3007' TO 3628' & NEVER DRILLED OUT CMT. PBTD = 2923'. 1ST PLUG AT 1352' WITH 12 SX GEL & 60 SX CMT. 2ND PLUG AT 552' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4452	4453		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
MAY - 4 2016
KCC DODGE CITY

SA

Form CP-2/3
720
5-18-16