

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-187-00143-00-00  
Spot: SE Sec/Twnshp/Rge: 3-27S-40W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: EDIGER Well #: 1-3  
County: STANTON Total Vertical Depth: 2345 feet

Operator License No.: 34997  
Op Name: CASILLAS PETROLEUM CORP  
Address: 348 RD DD  
SATANTA, KS 67870

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2343	0	WITH 400 SX CMT
SURF	8.625	309		WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/09/2016 8:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: KENT PENDERGARFT Company: CASILLAS PETROLEUM Phone: (620)287-4060

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE  
Date/Time Plugging Completed: 05/10/2016 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG STUCK IN HOLE. CUT TBG OFF AT 1791'. FISHED ADDITIONAL TBG OUT TO 1961'. COULD NOT GET BACK DOWN WITH OVERSHOT PAST 1888'. 5/9/16: SPOT 50 SX CMT W/2% CC AT 1888'. WAIT 2 HOURS. ATTEMPT TO LOAD CASING WITH WATER. COULD NOT. TAGGED HARD CMT AT 1030' WITH ELECTRIC LINE. SUSPECT HOLE IN CASING. RAN PACKER ON TBG & ISOLATED HOLE BETWEEN 0' & 29'. PERFORATE 4 HOLES AT 700'. RAN PACKER TO 478'. PUMP 50 SX CMT WITH HULLS IN LAST 10 SX. NO PRESSURE. PERFORATE 4 HOLES AT 320'. RUN PACKER ON 1 JOINT OF TBG. PUMP 43 BBLs WATER. TBG ON VACUUM. RUN PACKER TO 349'. PUMP 60 SX CMT WITH 2% CC ON VACUUM. SDON. 5/10/16: RAN PACKER TO 359'. PRESSURE TESTED SQUEEZE JOB TO 500#. HOLDING. PULL PACKER TO 29' & CIRCULATE CMT TO SURFACE THROUGH PERFS AT 320' USING 106 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2343	2345		
2294	2298		

Remarks: USED CLASS C COMMON CEMENT BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Ken Jehlik  
(TECHNICIAN)

RECEIVED  
MAY 11 2016  
KCC DODGE CITY

KCC WICHITA  
MAY 18 2016  
RECEIVED

Form CP-2/3  
20  
5-18-16