

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21143-00-00
Spot: NESWSW Sec/Twnshp/Rge: 19-21S-19W
990 feet from S Section Line, 990 feet from W Section Line
Lease Name: BRYANT GLENN Well #: 3-19
County: PAWNEE Total Vertical Depth: 4240 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2357	0	WITH 250 SX CMT
SURF	8.625	957		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/10/2016 9:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 524-1225

Proposed Plugging Method: 30 SX CMT WITH 100# HULLS AT 2337'. PERFORATE AT 700'. RUN TBG TO 1200' & PUMP 30 SX CMT. PULL TBG TO 700' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2016 3:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

PERFORATE AT 700'. RUN IN HOLE WITH 2 3/8" TBG TO 2337'. PUMP 30 SX CMT WITH 100# HULLS. PULL TBG TO 1200' & PUMP 30 SX CMT. PULL TBG TO 700' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TOP PLUG WAS 65 SX CMT. BOTH 4 1/2" CASING & ANNULUS FULL WHEN FINISHED CEMENTING.


Perfs:

Top	Bot	Thru	Comments
2274	2282		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed 
(TECHNICIAN)

RECEIVED
MAY 12 2016
KCC DODGE CITY

JA
KCC WICHITA
MAY 18 2016
RECEIVED

no
5-18-16