

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21864-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 19-33S-31W
4996 feet from S Section Line, 2235 feet from E Section Line
Lease Name: TUMBLEWEED Well #: 1-19
County: SEWARD Total Vertical Depth: 2760 feet

Operator License No.: 8967
Op Name: BARBOUR ENERGY CORPORATION
Address: PO BOX 13480
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2742	632	WITH 250 SX CMT
SURF	8.625	585		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/04/2016 12:30 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: LARRY ADAMS Company: LP ADAMS CONSULTING Phone: (405) 834-2236

Proposed Plugging Method: CIBP @ 2560' WITH 2 SX CMT. PLUG AT 1565' WITH 10 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/05/2016 10:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

5/4/16: TBG STUCK IN WELL. SHOT TBG @ 1506'. WOULDNT COME FREE. SHOT AGAIN AT 1375' WASNT FREE. SHOT AGAIN AT 1250'. 1ST PLUG AT 1229' WITH 25 SX CMT. CUT CASING AT 632'. 2ND PLUG AT 630' WITH 80 SX CMT. NO CIRCULATION. 5/5/16: RTIH TO 696' & COULDN'T TAG. PULL TBG TO 632' & BREAK CIRCULATION WITH MUD. PUMP 80 SX CMT AT 632' WITH GOOD RETURNS. PLUG AT 64' WITH 20 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
2642	2672		
2608	2632		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

K. Sullivan
JA

(TECHNICIAN)

RECEIVED
MAY - 9 2016
KCC DODGE CITY

no form CP-2/3
5-18-16