

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-175-21805-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 17-33S-31W  
349 feet from S Section Line, 2302 feet from E Section Line  
Lease Name: CLOVER Well #: 1-17  
County: SEWARD Total Vertical Depth: 2750 feet

Operator License No.: 8967  
Op Name: BARBOUR ENERGY CORPORATION  
Address: PO BOX 13480  
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2737	658	WITH 155 SX CMT
SURF	8.625	624		WITH 260 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/03/2016 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: LARRY ADAMS Company: LP ADAMS CONSULTING Phone: (405) 834-2236

Proposed Plugging Method: CIBP @ 2530' WITH 2 SX CMT. PLUG AT 1580' WITH 10 SX GEL & 50 SX CMT. PLUG AT 670' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/03/2016 2:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

5/2/16: TBG WAS STUCK. CUT IT AT 1601'. CUT 4 1/2" CASING AT 1552', WOULDN'T COME FREE. 5/3/16: RAN TBG TO 1512'. WOULDN'T GO ANY FURTHER. 1ST PLUG AT 1512' WITH 25 SX CMT. CUT 4 1/2" CASING AT 658'. 2ND PLUG AT 661' WITH 80 SX CMT. 3RD PLUG AT 64'-0'.

Perfs:

Top	Bot	Thru	Comments
2654	2664		
2624	2630		
2610	2620		
2578	2580		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]  
SA (TECHNICIAN)

RECEIVED  
MAY - 9 2016  
KCC DODGE CITY

Form CP-2/3  
Mo  
5-18-16