

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-40214-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 11-28S-6E  
3629 feet from S Section Line, 4287 feet from E Section Line  
Lease Name: LUCAS A Well #: 5  
County: BUTLER Total Vertical Depth: 2739 feet

Operator License No.: 5387  
Op Name: THE BUCKEYE CORPORATION DBA A  
Address: PO BOX 1020  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2734	100	40 SX
SURF	8.65	309		30 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2016 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: BRADY SHARP Company: AZTEC OIL CO. Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 2684 W/4 SXS, CIRC 360'-0'.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/10/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2680', DUMP BAILED 4 SXS CEMENT ON TOP OF SAND. 3-10-2016, TAGGED PLUG @ 2672'. RIH ON WIRELINE CUT CASING @ 360', LAYED DOWN 3 JOINTS 7" CASING, CASING HUNG UP IN HOLE. RIH W/2 3/8" TBG @ 350', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 90 SXS 60/40 POZMIX 4% GEL 1% CC TO SURFACE. CEMENT CIRCULATED, LAYED TBG DOWN, TOPPED WELL BACK TO SURFACE W/5 SXS. CONSOLIDATED OIL WELL SERVICES TICKET # 51185.

Perfs:

Top	Bot	Thru	Comments
2734	2739	OH	

Remarks: CEMENT ON BACKSIDE 8 5/8" SURFACE CASING / COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)  
KCC WICHITA  
MAY 16 2016  
RECEIVED

220  
5-18-16