

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40213-00-00
Spot: SESWNW Sec/Twnshp/Rge: 11-28S-6E
2974 feet from S Section Line, 4299 feet from E Section Line
Lease Name: LUCAS A Well #: 3
County: BUTLER Total Vertical Depth: 3037 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3024		267 SX
SURF	8.63	314		12 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/07/2016 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: BRADY SHARP Company: AZTEC OIL CO. Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 2974 W/4 SXS, CIRC 365'-0'.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/09/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CUT TUBING OFF @ 2970', & 600', LAYED DOWN 600' 2 3/8" TUBING. RIH W/TBG @ 588', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 20 SXS CLASS A COMMON 2% CC & DISPLACED IN CASING. TAGGED CEMENT @ 510'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 365-366 (2 SHOTS). RIH W/TBG @ 390', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 205 SXS 60/40 POZMIX 4% GEL, CEMENT DID NOT CIRCULATE. SDON. 3-9-2016, TAGGED PLUGS @ 158' INSIDE 5 1/2" CASING, & 250' OUTSIDE 5 1/2" CASING. RIH W/ 1" TBG ON BACKSIDE 5 1/2" @ 246', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 130 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TUBING. RIH W/2" TBG ON INSIDE 5 1/2" @ 158', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 20 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED TBG DOWN, TOPPED WELL BACK TO SURFACE W/10 SXS. CONSOLIDATED OILWELL SERVICES TICKET #'S 51183, & 51184.

Perfs:

Top	Bot	Thru	Comments
3024	3027	OH	

Remarks: TUBING & PACKER HUNG UP IN HOLE / COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger

KCC WICHITA

(TECHNICIAN)

MAY 16 2016

RECEIVED

Form CP-2/3

No 5-18-16

JK