

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-21077-00-00
Spot: SESWNWNW Sec/Twnshp/Rge: 34-26S-13W
4036 feet from S Section Line, 4884 feet from E Section Line
Lease Name: SOEKEN (DREWS) Well #: 2-34
County: PRATT Total Vertical Depth: 4449 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		
CIBP		4304		
CIBP		4344		
PROD	4.5	4448	1770	WITH 200 SX CMT
SURF	8.625	934		WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/26/2016 2:00 PM
Plug Co. License No.: 30481 Plug Co. Name: APOLLO ENERGIES, INC.
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES, INC. Phone: (620) 672-9001

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2016 3:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3930' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SQUEEZED TOPEKA PERFS WITH 50 SX COMMON CMT. PUMPED 30 SX CMT BEHIND 4 1/2" CASING & LEFT 10 SX CMT INSIDE OF 4 1/2" CASING. (SQUEEZED TOPEKA PERFS DUE TO BEING PERFORATED ABOVE CMT TOP BEHIND 4 1/2" CASING.) 1ST PLUG AT 980' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4256	4273		
4210	4213		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CMT & 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED
APR 29 2016
KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)

SA *NO 5-18-16*