

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21259-00-00  
Spot: E2NENWSW Sec/Twnshp/Rge: 10-27S-20W  
2326 feet from S Section Line, 4064 feet from E Section Line  
Lease Name: EINSEL TRUST Well #: 1  
County: KIOWA Total Vertical Depth: 4951 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4928	2424	WITH 125 SX CMT
SURF	8.625	597		WITH 310 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2016 4:30 PM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES Phone: (620) 672-9001

Proposed Plugging Method: CIBP @ 4800' WITH 2 SX CMT OR SAND TO 4800' WITH 4 SX CMT. PLUG AT 1325' WITH 15 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE  
Date/Time Plugging Completed: 05/12/2016 6:45 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SANDED TO 4800' WITH 4 SX CMT ON TOP OF SAND BRIDGE. 1ST PLUG AT 1322' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 654' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4853	4857		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
MAY 16 2016  
KCC DODGE CITY

KCC WICHITA  
MAY 18 2016  
RECEIVED

Form CP-2/3

20  
5-18-16