

9-27

1 040170

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,310 -0006

W/2 SW SE, SEC. 3, T 24 S, R 22 W/EX

660 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5303

Lease Name Hall "B" Well # 1

Operator: Canaday Oil Corporation

County Hodgeman 153.56

Name & Address 920 North Tyler, Suite 300

Well Total Depth 4725 feet

Wichita, KS 67212

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 367

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 East Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 9:50 a.m. Day: 27 Month: 9 Year: 19 88

Plugging proposal received from Bob Casper

(company name) White & Ellis Drilling Inc. (phone) 316-792-2424

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1474-99' Elevation 2307' GL

1st plug at 1500' with 50 sx cement, 2nd plug at 750' with 50 sx cement,

3rd plug at 380' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:15 p.m. Day: 27 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement,

2nd plug at 750' with 50 sx cement,

3rd plug at 380' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(XXXXX did not) observe this plugging.

DATE 10-10-88

INV. NO. 22548

Signed Stephen J. Pfeifer (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

OCT 6 10-6-88

CONSERVATION DIVISION Wichita, Kansas