

1-8-88

To: 1 030905
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-21,295-0000

SE NE NE, SEC. 35, T 24 S, R 23 W/E

4920 feet from S section line

330 feet from E section line

Lease Name Lonnberg Well # 1

County Hodgeman 153.79

Well Total Depth 4732 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 367

TECHNICIAN'S PLUGGING REPORT

Operator License # 5303

Operator: Canaday Oil Corporation

Name: 920 North Tyler

Address Wichita, KS 67212

Abandoned Oil Well Gas Well Input Well SHD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 East Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 8:30 p.m. Day: 8 Month: 1 Year: 19 88

Plugging proposal received from Bob Casper

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1472-99'

1st plug at 1500' with 50 sx cement, 2nd plug at 810' with 80 sx cement,

3rd plug at 390' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:45 p.m. Day: 8 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement,

2nd plug at 810' with 80 sx cement,

3rd plug at 390' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(SEEK / did not observe this plugging.

DATE 1-15-88

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 19579