

To: 1031416
STAFF CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

00100
API NUMBER 15-047-01,001 -0001

TECHNICIAN'S PLUGGING REPORT

Operator License # 31434
Operator: L & J Oil Properties, Inc.
Name:
Address 635 N. Stratford
Wichita, KS 67206

10-14
NW SE SE, SEC. 31, T 24 S, R 17 W/E
990 feet from S section line
990 feet from E section line
Lease Name McLean OWWO Well # 1.
County Edwards
Well Total Depth 4951 160.90 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 614

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor D.S.&W. Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1 p.m. Day: 14 Month: 10 Year: 1996

Plugging proposal received from Kent Strube
(company name) D.S.&W Well Servicing, Inc. (phone) 316-587-3361

Work: 5 1/2" at 4520' w/175 sx cement, PBTD 4510', Perfs at 4466-70'
1st plug sand back to 4416' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 14 Month: 10 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4416' and dumped 5 sx cement on top of sand
through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.

10-16-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2441' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 17 1996 observe this plugging.

DATE OCT 17 1996

INV. NO. 46711

Signed Steve Durrant
(TECHNICIAN)