

1 120241

MAR 29 1989

299 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,176-0000

SE SE SW, SEC. 34, T 24 S, R 17 W/8
330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name McKinney "E" Well # 1-34

Operator: F.G. Holl Company
Name & Address P.O. Box 780167
Wichita, KS 67207

County Edwards 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 29 Month: 3 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4592' PBTD 4563' Perfs at 4424-28'

1st plug pump 1 sx hulls and 25 sx cement at perfs, TOC 4130',

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

RECEIVED STATE CORPORATION COMMISSION

APR 4 1989 4-4-89

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: _____ Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 29 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement and pushed plug to 4130',

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-450 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2467' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(did / x /) observe this plugging.

INVOICED
DATE 4-19-89

Signed Dianne Rankin (TECHNICIAN)

INV. NO. 24338