

To: 1 090202
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-14 API NUMBER 15- 047-21,218-0000 236

C SE NW, SEC. 6, T. 24 S, R. 18 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5118
Operator: TGT Petroleum Corporation
Name
Address 209 E. William
Wichita, KS 67202

Lease Name Nightengale "A" Well # 1
County Edwards 150.47
Well Total Depth 4630 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 419

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor TGT Petroleum Corporation License Number 5118
Address 209 E. William, Wichita, KS 67202

Company to plug at: Hour: 10:30 a.m. Day: 14 Month: 7 Year: 1992

Plugging proposal received from Eldon Folmsbee
(company name) TGT Petroleum Corp. (phone) 316-262-6489

Work: 5 1/2" at 4629' w/250 sx cement, PBTD 4600', Perfs at 4081-84', 1213-0' with 275 sx cement
1st plug pump 300 lbs. hulls and 100 sx cement on bottom,
2nd plug pump 100 sx cement from 700-0'.
Check backside.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 14 Month: 7 Year: 1992

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement at 1 sx hulls over perfs,
2nd plug gel to 1040' from surface and 26 sx cement to 0'. Maximum pressure 1000 psi and
shut in 100 psi.
200 lbs. instant pressure on backside.

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1992
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 8-10-92
INV. NO. 35920

Signed [Signature] (TECHNICIAN)