


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 1 Twp. 24S Rge. 22W (~~X~~) (~~XXX~~)
Location as "NE/CNW/SW" or footage from lines S/2 SE/4 SW/4
Lease Owner E. L. Brooks
Lease Name Hall Well No. 1
Office Address 915 United Founders Tower, Oklahoma City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 27, 19 76
Application for plugging filed Verbal Application 19 76
Application for plugging approved Verbal Approval 19 76
Plugging commenced December 27, 19 76
Plugging completed December 27, 19 76
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,690 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	306'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,690 ft. (rotary total depth) to 900 ft. Set plug at 900 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 900 ft. to 300 ft. Set plug at 300 ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 300 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 15 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4-1/2 inch drill pipe.

1-25-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
Address 410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dean Britting, Agent ~~XXXXXX~~ of owner ~~XXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 No. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of January, 19 77

My commission expires June 30, 1978

Elsie Willison
Elsie Willison - Notary Public.



KANSAS GEOLOGICAL SOCIETY API NO. - 15-083-20,508-0000
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY E. L. Brooks

SEC. 1 T. 24S R. 22W
 LOC. S/2 SE/4 SW/4

FARM Hall

NO. 1

COUNTY Hodgeman
 KANSAS

TOTAL DEPTH 4,690'


COMM. December 15, 1976

COMP. December 27, 1976

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED January 20, 1977



CASING

20	10	
15	8-5/8"	306' cemented w/250 sxs cement
12	6	
13	5	

ELEVATION 2,326' KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	307'
Sand and Shale	1,433'
Anhydrite	1,441'
Shale	2,318'
Lime and Shale	3,948'
Lime	4,690'
Rotary Total Depth	4,690'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting

 Dean Britting

State of Kansas }
 County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 20th. day of January, 1977.

Elsie Willison

 Elsie Willison - Notary Public



My Commission Expires:

June 30, 1978