

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Garby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.--82-3-117

API NUMBER. 15-083-21,310-6000

LEASE NAME Hall "B"

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

660 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 3 TWP. 24 RGE. 22 (XXX(W))

COUNTY Hodgeman

Date Well Completed 9-27-88

Plugging Commenced 9-27-88

Plugging Completed 9-27-88

LEASE OPERATOR Canaday Oil Corp.

ADDRESS 920 N. Tyler - Suite 300, Wichita, KS 67212

PHONE#(316) 722-3840 OPERATORS LICENSE NO. 5303

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? YES

Which KCC Office did you notify? District #1

Is ACO-1 filed? NO If not, Is well log attached? NO

Producing Formation N/A ACO-1 and well log will be filed by Operator.  
Depth to Top \_\_\_\_\_ Bottom T.D. 4725

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	368'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Spotted 50 sx. cement @ 1500' thru drill pipe.

Spotted 50 sx. cement @ 750' thru drill pipe.

Spotted 40 sx. cement @ 380' thru drill pipe.

Spotted 10 sx. cement @ 40' thru drill pipe. Spotted 15 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and entries contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine  
401 E. Douglas - Suite 500

(Address) Wichita, KS 67202


OCT 5 1988

SUBSCRIBED AND SWORN TO before me this 4th day of October, 19 88  
Wichita, Kansas

My Commission Expires:

David F. Jamis  
Notary Public





# WHITE

AND ELLIS DRILLING, Inc.

## DRILLERS LOG

OPERATOR: Canaday Oil Corp., 920 N. Tyler - Suite 300, Wichita, KS 67212

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,  
Wichita, Ks. 67202

Lease Name Hall "B" Well No. 1

Sec. 3 T. 24 S R. 22 W Spot W/2 SW SE

County Hodgeman State Kansas Elevation \_\_\_\_\_

### Casing Record:

Surface: 8 5/8" @ 368' with 190 sx. 2% Gel 3% CC

Production: \_\_\_\_\_ @ \_\_\_\_\_ with \_\_\_\_\_ sx.

Type Well: D & A Total Depth 4725'

Drilling Commenced 9-19-88 Drilling Completed 9-27-88

Formation	From	To	Tops
Cellar	0	7	
Shale, Lime	7	4725	

RECEIVED  
STATE CORPORATION COMMISSION

OCT 5 1988

CONSERVATION DIVISION  
Wichita, Kansas

*Wichita*