

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 31 TWP. 24S RGE. 17W E/W
Location as in quarters or footage from lines:

SW NE NE

Locate Well
correctly on above
Section Platt.

Lease Owner Imperial Oil Company
Lease Name Wiltgen Well No. 2-31
Office Address 720 Fourth Financial Center Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 9-21-81
Plugging completed 9-24-81
Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom _____ T.D. 4530'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	598'	none
				4-1/2"	4529'	2778'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Moved in on location, plugged off bottom with 1 sack hulls, and 35 sacks cement. Pushed plug
to 4000'. Pulled 22" tension, shot pipe @3430', 3210', 2990' and 2770'. Pulled a total
of 65 joints of casing. Plugged well with 4 sacks hulls, 10 sacks gel, 50 sacks cement,
7 sacks gel, 8-5/8" plug, 35 sacks cement 8 sacks gel, 15 sacks cement. Plugging completed.

RECEIVED

STATE CORPORATION COMMISSION

SEP 29 1981

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

CONSERVATION DIVISION
Wichita, Kansas


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 19 81

My Commission expires:



Irene Hoover
Notary Public.