

15-047-20614-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County, Sec. 33 Twp. 24S Rge. 17W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SE

Lease Owner Sterling Drilling Company, et al
Lease Name Bernstorf #1 Well No. 1
Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed January 31, 19 80
Application for plugging filed January 31, 19 80
Application for plugging approved January 31, 19 80
Plugging commenced 3:30 PM, January 31, 19 80
Plugging completed 6:00 PM, January 31, 19 80
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production
Yes 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4575'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	307'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud to surface with 40 sacks 50/50 Pozmix
through drill pipe at 540'; 40 sacks through
drill pipe at 270'; heavy mud to 40' with Howco
plug and 1/4 sackx hulls; 10 sacks to surface
with 5 sacks in rathole.

80
4

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE
F. A. Wuellner (employee of owner) or (owner, or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 19 80.



Charles M. Hall
Charles M. Hall, Notary Public.

My commission expires _____

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- BERNSTORG #1
Located: SE SE, Section 33-24S-17W, Edwards County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 23, 1980
COMPLETED: January 31, 1980

TOTAL DEPTH: 4575'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 40 Sand and Clay	Ran 7 joints 8 5/8" OD, 28# casing. 296'
40 - 830 Shale, Red Bed	set at 307' K.B. Cemented with 250 sacks
830 - 1800 Shale	60/40 Pozmix with 2% gel and 3%cc. Plug
1800 - 3730 Lime and Shale	down at 2:45 AM, 1-24-80, by Howco.
3730 - 3925 Lime	
3925 - 4085 Lime and Shale	
4085 - 4380 Lime	
4380 - 4440 Lime and Shale	
4440 - 4450 Lime	
4450 - 4500 Lime and Shale	
4500 - 4570 Lime	
4570 - 4575 Lime and Shale	Plugged.

RECEIVED
STATE GEOLOGICAL COMMISSION

FEB - 4 1980

REGISTRATION DIVISION

Deviation Surveys:

2° at 2285'
1 3/4° at 4575'