

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047,21,176-6000

LEASE NAME McKinney 'E

WELL NUMBER #1-34

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 34 TWP. 24S RGE. 17W (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 3/23/89

Plugging Completed 3/29/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl Company

Box 158

ADDRESS Belpre, KS 67519

PHONE# (316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4680

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	300	none
				4 1/2	4592	2410

4-5-89
RECEIVED
STATE CORPORATION COMMISSION
APR 5 1989
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Bottom was plugged with 25 sacks cement top @4130', shot @2410', plugged surface with 400# hulls, 10 gel, 50 sacks cement, 10 gel, 100# hulls, 8 5/8" plug, 120 sacks 60/40 poz 6%gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of April, 19 89

Notary Public

My Commission Expires:



15-047-21176-0000

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - McKINNEY "E" 1-34

Located: SE SE SW, Section 34-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 10, 1984

COMPLETED: May 16, 1984

TOTAL DEPTH: 4600'

LOG

CASING RECORD

0 - 95 Surface Soil and Sand
 95 - 189 Sand and Shale
 189 - 303 Shale and Clay
 303 - 650 Shale, Sand, Red Beds
 650 - 1110 Shale
 1110 - 1166 Anhydrite
 1166 - 1750 Shale, Lime Stringers
 1750 - 4450 Lime and Shale
 4450 - 4460 Chert
 4460 - 4600 Lime and Shale

Ran 7 joints new 8 5/8", 23# casing.
 288.28' pipe set at 300' K.B.
 Cemented with 250 sacks 60/40 Pozmix,
 plus 3% cc. Plug down at 7:30 PM,
 5-10-84, by Howco.

Ran 114 joints 4 1/2", 10.5# casing.
 11 joints were used. 4582.97' pipe
 set at 4592' K.B. Cemented with 100
 sacks Lite, 125 sacks Pozmix plus our
 regular additives. Plugged rathole - did
 not plug water well. Plug down at 10:15
 PM, 5-16-84, by Howco.

Deviation Surveys: 1° at 2230'
 3/4° at 4460'