


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

PE

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 27 Twp. 24 Rge. 12 (X) W (W)
Location as "NE/CNW/SW" or footage from lines C SE NW NW
Lease Owner Cooperative Refinery Association
Lease Name Byer "B" Well No. 4
Office Address Drawer C - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Salt Water Disposal
Date well completed February 23 19 53
Application for plugging filed June 26 19 61
Application for plugging approved June 27 19 61
Plugging commenced July 26 19 61
Plugging completed July 31 19 61
Reason for abandonment of well or producing formation Plugged oil wells,
did not need disposal.
If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4476 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	309	
				5-1/2	4127	1881'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dig deadman holes, pull fence around well. Rig up, make blocking out of 5 1/2" pipe under rig sills, sand 4163' to 4110'. Dump 5 sax cement. Load hole with water, unpack braden head, work pipe 18", shot pipe at 2500'. Pump pressure to 1200#, shoot at 2300' pressure to 1200#. Shoot at 2100', pressure to 1200#. Shoot at 1880', work pipe loose. Pull 75 joints pipe, total 1881'. Haul mud and mud hole. Mud to 270', haul cement, water and rock. Pump out cellar, 10' rock bridge 270' to 260'. Dump 20 sax cement, mud to 40'. 10' rock bridge, dump 10 sax cement. Well completed and approved by State Plugger, Frank Broadfoot.

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1961
CONSERVATION DIVISION
Wichita, Kansas
8-9-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Comstock Casing Pulling Company
Address Stafford, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arthur J. Robinson
Drawer C - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of August, 19 61

My commission expires April 4, 1964
Barbara J. Marquardt
Notary Public.



Byer "B" #4
 Owner: Cooperative Refinery Association
 Contractor: Edwards Drilling Company
 Commenced: 2-6-53
 Completed: 2-23-53

C-SE-NW-NW
 27-24-12W Stafford County, Kansas

Casing Records: 8-5/8" @ 309'
 w/ 200 ex.

5 1/2" @ 4127 w/ 125 ex.

Elevation: 1874' D.F.

Formation	From	To
Shale	0	120
Lime, Shale	120	180
Sand	180	250
Shale & Red Rock	250	690
Lime	690	715
Shale & Shells	715	1065
Sandy Shale	1065	1250
Salt	1250	1100
Shale w/ lime stks.	1100	1620
Lime	1620	2115
Lime (shale stks)	2115	2510
Lime	2510	2527
Cherty Lime	2527	2625
Lime	2625	2670
Cherty Lime	2670	2685
Lime (shale stks)	2685	2725
Shale	2725	2770
Shaley Lime	2770	2910
Shale w/ lime stks	2910	3010
Shale	3010	3100
Shale & Lime stks.	3100	3215
Lime	3215	3260
Shale	3260	3340
Shale & Lime stks.	3340	3380
Brown Lime & Shale	3380	3440
Lime	3440	3445
Shale	3445	3514
Lime	3514	3820
Lime & Shale	3820	3845
Shale	3845	3919
Shale	3919	3950
Lime	3950	3995
Lime (streaks of chert)	3995	4063
Shale	4063	4087
Sand	4087	4113
Lime	4113	4166
RTD	4166	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 9 1961
 CONSERVATION DIVISION

- Top Arb

1874
 2292

(State of Kansas)
 (County of Barton)

I hereby certify that the above is a true and correct copy of the log on the Byer "B" #4 well, located C-SE-NW-NW of Section 27-24-12W, Stafford County, Kansas.

L. M. Collins

Subscribed and sworn to before me this 17 day of March 1953.

Chas. E. Elliott

My commission expires: 2-20-57