


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 27 Twp. 24 Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines C/S₂-S₂-NW₄
 Lease Owner Cooperative Refinery Association
 Lease Name Byers "B" Well No. 6
 Office Address Box 765 Great Bend, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry
 Date well completed April 22 19 55
 Application for plugging filed May 9 19 55
 Application for plugging approved May 9 19 55
 Plugging commenced May 5 19 55
 Plugging completed May 5 19 55
 Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4086 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	303'	
				5 1/2"	4085 1/2'	99 joints

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set Halliburton bridging plug @ 3500, filled up 20' with sand.
Shot pipe off at 3102'. Filled hole with heavy mud to 300'. Set rock bridge, cemented with 20 sacks. Set rock bridge @ 35'.
Cemented to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Cooperative Refinery Association
 Address Box 765 Great Bend, Kansas


STATE OF KANSAS, COUNTY OF BARTON, ss.
E. A. Ivey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. A. Ivey
Box 765 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 13 day of May, 19 55

My commission expires August 17, 1957

24-7368-5 3-53-20M



Notary Public.
STATE CORPORATION COMMISSION

5-13-55

COPY

15-185-12440-0000

DRILLERS LOG

Byers B #6

Loc: CS $\frac{1}{2}$ -S $\frac{1}{2}$ -NW $\frac{1}{4}$
Sec: 27-24-12W
Stafford County, Kansas
Operator: Cooperative Refinery Association
Contractor: Company Rig #5

Elevation: 1879D.F.
Casing: 8 5/8" @ 303' w/200 sx.
posmix, 2 C.C.

5 1/2" @ 4085 1/4 w/ 150 sx.
common

Comm: 4-5-55 Comp: 4-22-55
Total Depth: 4086 (Corrected)

From	To	Formation
0	150	Surface, clay and sand
150	303	Shale and shells
303	425	Red bed, sand
425	1325	Shale & shells
1325	1810	Shale & lime
1810	2110	Lime
2110	3195	Lime & Shale
3195	3255	Lime
3255	3335	Lime & Shale
3335	3430	Lime
3430	3515	Lime & shale
3515	3880	Lime
3880	3920	Lime & shale
3920	3932	Lime
3932	4040	Cherty Lime
4040	4086	Lime
4086		R.T.D.

(STATE OF KANSAS)

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the
Byers "BW" #6 well, located CS $\frac{1}{2}$ -S $\frac{1}{2}$ -NW $\frac{1}{4}$ of Section 27-24-12W, Stafford County, Kansas.

P. W. Jackson

Subscribed and sworn to before me this 26 day of April, 1955

Donald E. Hunt

My commission expires: August 17, 1957

RECEIVED
STATE CONSERVATION COMMISSION
MAY 13 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
WELL SEC 27 T 24 R 12W
BOOK PAGE 117 LINE 28