


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Stafford County, Sec. 27 Twp. 24 Rge. 12 (E) (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNWxSWx" or footage from lines \_\_\_\_\_  
Lease Owner Morganstern  
Lease Name Jenkins Well No. \_\_\_\_\_  
Office Address 231 South Dellrose Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 6/18/59 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 6/25/59 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back to 3455 ft. with sand and dumped 5 sacks of cement.  
Bailed hole down to 300 ft. set 10 ft. rock bridge dumped 20  
sacks cement filled hole with mud to 40 ft. set 10 ft. rock  
bridge dumped 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 25 1959

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. & L Casing Pulling Co.  
Address 1416 Coolidge Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgewick, ss.  
Operator (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arthur Morganstern  
P.O. Box 2546 - Wichita, K., K. (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of August, 1959

My commission expires Jan. 23, 1960 Phyllis M. Jones Notary Public.

PLUGGING  
FILE SEC. 27 24 R. 12  
BOOK PAGE 44 LINE 19

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company- MIDSTATES OIL CORP.  
Farm- W. R. Jenkins No. 1

SEC. 27 T. 24 R. 12W  
NW NW SE

Total Depth. 4071  
Comm. 8-11-52 Comp. 8-30-52  
Shot or Treated.  
Contractor. H. B. Armer  
Issued. 10-4-52

County Stafford  
KANSAS



Elevation. 1878

Production. 324 BO & 5% wtr.

Figures Indicate Bottom of Formations.

surface clay & shale	45
sand	145
red bed & shale	750
shale & shells	960
anhydrite	990
shale & shells	1330
lime & shale	1650
lime broken	1805
lime & shale	1855
sand hrd sharp	1870
lime sandy	1905
shale & shells	1975
lime & sand	1990
shale & lime	2585
shale & shells	2900
shale & lime	3550
lime	3610
lime & chert	3616
lime	3850
lime & shale	3921
core	3946
lime & chert	4010
lime	4040
lime & sand	4058
shale & sand	4065
sand & lime	4068
cored	4071 RTD
Total Depth	

Scout Tops:	
Heebner	3339
Brown Lime	3490
Lansing	3513
Viola	3920
Simpson	4048
1st Simpson Sand	4063
2nd Simpson Sand	4066

RECEIVED  
STATE CORPORATION COMMISSION

JUN 9 1959

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING

FILE SEC. 27 T. 24 R. 12W  
BOOK PAGE 44 LINE 19