


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Kingman County, Sec. 10 Twp. 28S Rge. 10 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SW
Lease Owner Kenneth Alfred Ellison
Lease Name Wagner Well No. 1
Office Address 222 N. E. 50th Street, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 21, 1952
Application for plugging filed June 21, 1952
Application for plugging approved June 21, 1952
Plugging commenced June 21, 1952
Plugging completed June 21, 1952
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plot

If a producing well is abandoned, date of last production -- 19--
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, Box 597, McPherson County, Kansas
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 4564 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.
Mud from T. D. to 270'
Wood Plug @ 270'
15 sacks cement @ 269
Mud to 35'
Wood Plug @ 35'
5 sacks cement @ 34'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Co.
Address Petroleum Building, Wichita, Kansas

STATE OF Oklahoma, COUNTY OF Oklahoma, SS.
R. Lloyd Hoagland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Lloyd Hoagland
R. Lloyd Hoagland
222 N. E. 50th Street, Oklahoma City, Okla.
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1952
[Signature]
Notary Public.

My commission expires December 27, 1955
23-8390-s 6-51-20M

PLUGGING
FILE SEC 10 T 28 R 10 W
25

RWD 07-01-52

Jacob E. Lemmons

Petroleum Geologist
 Telephone 63-2325
 1102 N. Delaware Ave.
 WICHITA 14, KANSAS

June 23, 1952

GEOLOGIC REPORT

Wellson #1 Wagner
 NE 1/4 SW 10-28-10W
 Wildcat
 Kingman County, Kansas

Contr.: Beardmore DrLg. Co.
 HL.: 1701 DF
 1504 EB

The Wellson #1 Wagner was drilled with rotary tools to 4564' Total Depth. Ten foot samples were kept from 2500-3500', and 5' samples from 3500-4564' Total Depth. One minute drilling time was kept from 3200-4564' Total Depth. A Schlumberger Salt Mud Log was run with detailed portion from 3500-4564' Total Depth.

Two hundred eighty-two feet of 8 5/8" surface casing was cemented.

<u>Formation Tops</u>	<u>FORMATION TOPS</u>	
	<u>Depth Below</u> <u>Surface</u>	<u>Sea Level</u> <u>Datum</u>
HEMBUSH	3354	-1660
TORONTO	3370	-1686
DOUBLEDAY	3421	-1717
BROWN LEANING	3536	-1832
LANSING	3555	-1851
MISSISSIPPI	4074	-2370
KILDAREHOCK	4248	-2444
VIOLA	4356	-2552
STAPSON	4416	-2612
ARBORELLA	4532	-2628
TOTAL DEPTH	4564	-2680

RECEIVED
 STATE GEOLOGICAL SURVEY
 WICHITA, KANSAS

GEOLOGICAL SURVEY DIVISION
 WICHITA, KANSAS

Wagner No. 1

NE NE SE
Section 10-28S-10W
Kingman County, Kansas

Drilled by: Beardmore Drilling Company
Drilled for: Kenneth A. Ellison

Casing Record:

8-5/8 282' w/150 Sacks Cement

Date Commenced: June 5, 1952
Date Completed: June 21, 1952

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5
Surface Soil	15
Sand	110
Red Rock Shale & Shells	282
Red Rock	425
Shale & Shells	1440
Broken Lime	2195
Lime & Shale	3470
Lime	4564 T. D.

D & A

TOPS:

Heebner	3364
Toronto	3392
Brown Lime	3536
Lansing	3559
Mississippi	4074
Azbuckle	4532

DST #1 - 4074 to 4081 - open 1 1/2 hours, recovered 61 feet of slightly oil cut mud. Shut in 15 minutes, BHP 260#.

DST #2 - 4460 to 4469 - open 30 minutes, recovered 12 feet of mud. Shut in 15 minutes, BHP 1275#.

Elevation: DF 1701
GR 1699

RECEIVED
STATE COMMERCE COMMISSION

JUL 1 1952

STATE OF KANSAS

CONSERVATION DIVISION
Wichita, Kansas

COUNTY OF SEDGWICK

SS

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the above-described, to the best of my knowledge and belief.

Gene Beardmore

Subscribed and Sworn to before me this 24th day of June, 1952

Leonard P. Tolle
Notary Public

My Commission Expires: January 28, 1956

PLUGGING
DEC 21 1952
PAGE 28 LINE 60