


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Kingman County, Sec. 36 Twp. 28 Rge. (E) 9 (W)  
Location as "NE/CNWxSWx" or footage from lines. 150' West of C NW SE  
Lease Owner Pickrell Drilling Company  
Lease Name Beat "C" No. 1 Well No. 1  
Office Address 705 4th National Bank Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 11, 1966  
Application for plugging filed February 11, 1966  
Application for plugging approved February 11, 1966  
Plugging commenced February 11, 1966  
Plugging completed February 11, 1966  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4541 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	217'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 200'. Set plug. Cemented with  
25 sacks cement. Heavy mud to 40'. Set plug.  
Cemented with 10 sacks cement to bottom of  
cellar. Plugged rat hole with 2 sacks cement.

STATE CORPORATION COMMISSION

FEB 23 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 4th Natl Bank Building, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. SEBITS

(Notary Public) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits  
705 4th Natl Bank Bldg, Wichita 2, Kansas  
(Address)

Subscribed and sworn to before me this 16th day of February, 1966

My commission expires June 21, 1966  
Maxine Blackman  
Notary Public.



ROTARY DRILLING LOG

15-095-30088000

COMPANY: PICKRELL DRILLING COMPANY  
705 4th National Bank Building  
Wichita, Kansas

Rotary Drilling Commenced 1-28-66

Rotary Drilling Completed 2-11-66

LOCATION: Beat "C" No. 1, 150' West of C NW SE Section 36-28-9W, Kingman County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: (10 jts) 8 5/8" surface casing set at 217', cemented with 145 sacks cement. Circulated. Completed 6:00 P.M. January 28, 1966. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Sand	C. F. S.
218	Red Rock	3876
850	Red Bed & Shale	3913
1500	Shale, Shells & Lime	4163
3560	Lime & Shale	4201
3675	Lime	4458
3728	Lime & Shale	4465
3830	Lime	4475
3876	Lime & Shale	4485
4000	Lime	4495
4148	Lime & Shale	4523
4201	Mississippi Chert	4541
4270	Mississippian	
4317	Lime & Shale	
4370	Kinderhook	<u>Slope Tests</u>
4485	Shale & Lime	1500
4523	Viola	2500
4541	Viola Lime - RTD	3500
		4100

S. L. M.  
2672  
3560  
4389

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 23 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By: C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS  
COUNTY OF SEDGWICK } ss.:

On this 16th day of February, 1966, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman  
Maxine Blackman, Notary Public