

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Be and Affidavit
Mail or Report to:
Conservation Division
State Corporation Commission
800 Pitting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec 33 Twp. 24S Rge. (E) 14 (W)
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 1650 Fr. S. 330 Fr. W. of SE/4
 Lease Owner Phillips Petroleum Co.
 Lease Name Waters Well No. 1
 Office Address Bartlesville, Okla.
 Character of Well (completed as Oil, Gas or Dry Hole) Dry
 Date well completed 10-18-46 19
 Application for plugging filed 10-18-46 19
 Application for plugging approved 10-18-46 19
 Plugging commenced 10-19-46 19
 Plugging completed 10-20-46 19
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? YES

Name of Conservation Agent who supervised plugging of this well H.W. Kerr
 Producing formation Arbuckle Depth to top 4321 $\frac{1}{2}$ Bottom 4432 $\frac{1}{2}$ Total Depth of Well 4432 $\frac{1}{2}$ Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
L.K.C.	Dry	3708 $\frac{1}{2}$		8 5/8"	924.61	0
Miss.	"	4082 $\frac{1}{2}$				
Kinderhook	"	4101 $\frac{1}{2}$				
Simpson	"	4269 $\frac{1}{2}$				
Arbuckle	"	4321 $\frac{1}{2}$	4432 $\frac{1}{2}$			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud to 250' - Ran 20 sacks cement - filled
 with mud to 30' - ran 10 sacks cement to cap, filling
 to base of cellar. Plugging completed 4 AM. 10-20-46.

PLUGGING
 FILE 33 24 14W
 BOOK PAGE 77-16

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to N.C. Mortimer
 Address Great Bend, Kans. Box 779

11-22-46

STATE OF Kansas, COUNTY OF Barton, ss.

N.C. Mortimer (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
 described well as filed and that the same are true and correct. So help me God.

(Signature) *N.C. Mortimer*
 Great Bend, Kans. Box 779
 (Address)

11-22-46

SUBSCRIBED AND SWORN to before me this 18 th. day of NOV.

Notary Public
[Signature]
 19.46

My commission expires Mar. 27, 1950

Formation Record

Lease **Waters**

Well No. **1**

FROM	TO	Formation	REMARKS
0	240	Sand and shale.	
240	700	Shale and red bed.	
700	950	Shale and shells.	
950	950	Anhydrite.	
950	1050	Red bed.	
1050	1700	Shale and shells.	
1700	3232	Lime and shale.	
3232	3580	Lime.	
3580	3680	Lime and shale.	
3680	4074	Lime	Top I.K.C. 3709 1/2 D.F.
4074	4088	Lime and shale.	Top Miss. 4082 1/2 D.F.
4088	4104	Lime.	Top Hinderhook 4101 1/2 D.F.
4104	4138	Lime and shale.	
4138	4174	Lime, cherty.	
4174	4216	Lime.	
4216	4252	Lime, cherty.	
4252	4277	Lime.	Top Simpson. 4269 1/2 D.F.
4277	4350	Lime and shale.	Top Arbuckle 4321 1/2 D.F.
4350	4432 1/2	Lime, T.D. D.F.	

FILE **33 24 140**
 BOOK **79-NE-16**

