


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 33 Twp. 24 Rge. 14 (E) (W)

Location as "NE/CNWxSWx" or footage from lines. NE NE NW
Lease Owner: H.C. Bennett
Lease Name: Waters Well No. 1
Office Address: 1212 Union Nat'l Bldg. Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole): Oil Well
Date well completed: 7-29-63 19
Application for plugging filed: 12-3-66 19
Application for plugging approved: 12-5-66 19
Plugging commenced: 12-7-66 19
Plugging completed: 12-12-66 19
Reason for abandonment of well or producing formation: depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production: 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Archie Elving
Producing formation: Depth to top: Bottom: Total Depth of Well: 4261 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	252'	none
				5 1/2	3976'	2414'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with sand to 3800' and dump 5 sacks of cement

Set 10' rock bridge from 240' to 230' and mix and dump 5 sacks of cement, left set overnight

Bail hole down to bridge and dump 25 sacks of cement

Mud hole to 40', rock to 30' and dump 10 sacks of cement to surface

STATE CORPORATION COMMISSION

DEC 28 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Flint Engineering and Const. Co.
Address: 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *James Lewis*

(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of December, 1966

Ronald R. Hanson

Notary Public.

My commission expires Sept. 27, 1967

Rest. Brown

ROTARY DRILLERS' LOG

OPERATOR: John C. Graves & Petroleum, Inc. DRILLING COMMENCED: July 24, 1963
 Box 332, El Dorado, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: July 29, 1963
 Box 332, El Dorado, Kansas

CASING RECORD: 4 Jts. - 242' 8-1/8" new LOCATION: Waters No. 1
 surface with 22# sacks. 1E NE NW
 126 Jts. - 3476' 1-1/2" Section 33-24S-14W
 casing with 22# sacks. Stafford County, Kansas

0 - 120	Sand	3701 - 3705	Shale
120 - 238	Shale	3705 - 3935	Lime
238 - 251	Shale & lime streaks	3935 - 4022	Shale & lime
251 - 970	Shale	4022 - 4079	Lime
970 - 1600	Shale & shells	4079 - 4082	Lime & shale
1600 - 1795	Shale & lime streaks	4082 - 4110	Chert & cherty lime
1795 - 1940	Lime & shale streaks	4110 - 4159	Lime
1940 - 2330	Lime & shale	4159 - 4181	Lime & chert
2330 - 2530	Shale & lime streaks	4181 - 4240	Chert
2530 - 335	Shale & lime	4240 - 4261	Lime & chert
335 - 3578	Lime	4261	Rotary Total Depth
3578 - 3701	Shale		

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John C. Graves*
President

P.B. T.D. = 3975'
Top of Perf. = 3836'
Sand to 3800 + 5 st.

STATE OF KANSAS)
) SS
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 31st day of July, 1963.

My commission expires

Betty Brandt
Betty Brandt Notary Public

Copy to Corporation Commission
Copy to Well Log Bureau