

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21291-0000

LEASE NAME Budde #1

WELL NUMBER _____

SPOT LOCATION 100' S NW NE SW

SEC. 27 TWP. 24 RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 2/7/84

Plugging Completed 2/13/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Energy, Inc.

ADDRESS 105 N. Main, Suite 415, Wichita, Ks. 67202

PHONE # () 265-2261 OPERATORS LICENSE NO. #5230

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	310'	none
				4 1/2"	4099'	2031'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3600', & 4 sacks cement. Shot pipe at 3100', 3000', 2900', 2400', & 2030'. Layed down 51 joints. Plugged well with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug, & 125 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrrell Kelso

(Address) Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

FEB 16 1984

SUBSCRIBED AND SWORN TO before me this 14th day of February, 1984

CONSERVATION DIVISION
My Comm. Expires _____



Irene Hoover
Notary Public

DRILLERS LOG

OPERATOR: Petroleum Energy, Inc. 710 One Twenty Bldg. Wichita, Ks. 67202
CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Budde Well No. #1
Sec. 27 T. 24 R. 12W Spot 100' S NW NE SW
County Stafford State Kansas Elevation _____

Casing Record:

Surface: 8 5/8 @ 310' with 165 Sxs. 3%cc
2%gel
Production: _____ @ _____ with _____ Sxs.

Type Well: Oil Total Depth 4100'

Drilling Commenced: 5-23-81 Drilling Completed 6-1-81

Formation	From	To	Tops
Cellar	0	7	
Shale	7	1709	
Shale, Lime	1709	3345	
Lime	3345	4100	

RECEIVED
STATE CORPORATION COMMISSION
FEB 06 1984
CONSERVATION DIVISION
Wichita, Kansas

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production: _____

Electric Log	Type and Depths Covered