

15-095-01505-0000

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 7 1963  
11-07-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Rains & Williamson Oil Co. and Mull Drilling Co., Inc.

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name Graber Well No. # 1

Location C NW SE NE Sec. 36 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 4500

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor: Rains & Williamson Oil Co.

Address: 412 Union Center, Wichita, Kansas License No.   

Operation Completed: Hour 7:45PM Day 4th Month Nov. Year 1963

The Above well was plugged as follows:

299' of 8 5/8" surface pipe, cemented with 150 sacks. Hole was filled with  
drilling mud to 290', 1st cementing plug, bridged with 1/2 sack hulls,  
cemented with 25 sacks. Hole was filled with drilling mud to 40', 2nd  
cementing plug, bridged with 1/2 sack hulls, cemented with 10 sacks to  
base cellar. Rat hole bridged with plug and cemented with 5 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 11/8/63  
INV. NO. 8037-W

Signed: Archie Elving  
Well Plugging Supervisor