

KANSAS

15-095-30058-0000

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN -1 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Hibbs Well No. # 1

Location C NE NW Sec. 16 Twp. 29 Rge. 8 (E) (W) W

County Kingman Total Depth 4435'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kansas License No.     

Operation Completed: Hour 11:00AM Day 25th Month May Year 1966

The Above well was plugged as follows:

253' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole  
was filled with drilling mud to 250', 1st cementing plug, bridged with  
1/2 sack of hulls on fluid at 250', and cemented with 30 sacks, through  
the drill pipe. Hole was filled with drilling mud to 50', 2nd cementing  
plug, bridged with 1/2 sack of hulls on fluid at 50', and cemented with  
25 sacks to the base of the cellar. Rat and mouse holes bridged and  
cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 6/1/66  
INV. NO. 3321-W