


15-095-20001-0000

Form CP-3  
Rev. 6-26-62

 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Intent to Drill, filed  
January 6, 1967

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 17 1967  
01-17-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Leben Drilling, Inc.

Complete Address: Box 486 GREAT BEND  
815 Wichita Plaza, Wichita, Kansas

Lease Name Bock Well No. # 1

Location C SW NE Sec. 17 Twp. 29 Rge. 8 (E) (W) W

County Kingman Total Depth 4560'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza, Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 1:00PM Day 16th Month Jan. Year 1967

The Above well was plugged as follows:

208' of 8 5/8" surface pipe, cement circulated with 150 sacks. Hole  
was filled with drilling mud to 200', 1st cementing plug, bridged with  
1 sack of dry cement and 1/2 sack of hulls on fluid at 200', and cemented  
with 24 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid  
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/17/67  
INV. NO. 4629-11

Signed: Archie Elving  
Well Plugging Supervisor