

15-095-20061-0000

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Well Plugging Authority,
issued February 15, 1968.

Operator's Full Name Leben Drilling, Inc.

Complete Address: Box 486, Great Bend, Kansas 67530

Lease Name Rohlman Well No. # 1

Location C SE NE Sec. 18 Twp. 29 Rge. 8 (E) (W) W

County Kingman Total Depth 4207'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 2:00PM Day 3rd Month March Year 1968

The Above well was plugged as follows:

209' of 8 5/8" surface pipe, cemented with 150 sacks. 4207' of 4 1/2" long
string, cemented with 100 sacks. Plug back T.D. 4200'. Top perforation 4188'.
10 sacks of cement was pumped on bottom, with the top of the cement at 4100'.
3650' of 4 1/2" long string was recovered from the hole. Hole was filled with
mud to 205', rock bridge from 205' to 195', and cemented with 25 sacks, with
cement from 195' to 120'. Hole was filled with mud to 40', rock bridge from
40' to 30', and cemented with 10 sacks, with cement from 30' to the base of
the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 3/7/68
INV. NO. 7377-W