

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-00627-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 24-30S-8W  
330 feet from S Section Line, 2970 feet from W Section Line  
Lease Name: JOE TJADEN Well #: 2-24  
County: KINGMAN Total Vertical Depth: 4420 feet

Operator License No.: 34357  
Op Name: ATLAS OPERATING LLC  
Address: 15603 KUYKENDAHL, STE 200  
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4350		
PROD	5.5	4716		250 SX
SURF	9.63	197		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/19/2016 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ZAFAR ULLAH Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/28/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

PULL OUT OF HOLE WITH 47 RODS PARTED. TUBING PART AT 3'. LATCH TUBING WITH OVER SHOT. UNABLE TO WORK TUBING LOOSE. RUN IN WITH ROD FISHING TOOL & LATCH ONTO ROD FISH. PULL OUT OF HOLE WITH RODS AND PUMP. MOVE IN WIRELINE UNIT. LATCH ONTO TUBING WITH OVERSHOT. SHOOT OFF TUBING @ 4109. COULD NOT FREE. SPLIT SHOT @ 3900'. UNABLE TO FREE TUBING. PUMP 35 SX CLASS A CEMENT, 150 LBS HULLS, 3% CC. AND DISPLACE TO ABOUT 3700'. SHOT OFF TUBING AT 1300' - DID NOT GET FREE. PERFORATE TUBING AT 1200' AND PUMP 35 SX CLASS A CEMENT, 3% CC. RUN IN TO TAG NO CEMENT. PUMP ANOTHER 35 SX 3% CC. RUN IN NO CEMENT TAG. PUMP 35 SX 3% CC. NO TAG. PUMP 35 SX CEMENT, 3% CC, 50 LBS HULLS, PRESSURE UP TO 200#. RUN IN AND TAG CEMENT AT 890'. SHOOT TUBING FREE AT 810'. PULL OUT LAY DOWN TUBING. PERFORATE CASING @ 800. PUMP 50 SX CEMENT 150 LBS HULLS. TAG AT 670'. RUN TBG TO 250 PUMP 75 SX CIRCULATED OUT 5 1/2" CASING. PULL TUBING OUT. HOOK UP TO 5 1/2" CASING PUMP 75 SKS DOWN CASING CIRCUALTE CEMENT OUT 9 5/8" SURFACE CASING. BACKSIDE FELL BACK 45', TOPPED WITH 25 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4366	4376		
4304	4326		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB. PAST 10 YEAR TA.

Plugged through: TBG

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAY 23 2016

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*220*  
*6-9-16*

*✓*