

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00631-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 24-30S-8W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: JOE TJADEN Well #: 3-24
County: KINGMAN Total Vertical Depth: 4400 feet

Operator License No.: 34357
Op Name: ATLAS OPERATING LLC
Address: 15603 KUYKENDAHL, STE 200
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4399		250 SX
SURF	9.63	214		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ZAFAR ULLAH Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 04/21/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

RUN IN HOLE WITH TUBING TO 900'. FELL THROUGH BRIDGE AT 900'. WENT IN HOLE TO 4025'. PUMP 35 SX CEMENT, 150 LBS HULLS 3% CC. @ 4025'. TAGGED CEMENT AT 3870'. PERFORATE 5 1/2" CASING AT 1200' PUMP 35 SX CLASS A CEMENT. PERFORATE @ 800' AND 260'. TAG PLUG AT 1015. RUN TUBING TO 800'. SPOTTED 50 SX CEMENT 100 LBS HULLS 3% CC. SPOTTED 75 SX CEMENT AT 260' NO CIRCULATION. TAG CEMENT AT 560'. RUN TUBING TO 260'. PUMP 10 BBLs WATER, MIX 5 SACKS GEL, 80 SX CEMENT CIRCULATE OUT 5 1/2". PULL OUT AND LAY DOWN TUBING. HOOK UP TO 5 1/2" CASING. PUMP 60 SX CEMENT CIRCULATED OUT 9 5/8" SURFACE. TOP WELL OFF WITH 5 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4287	4352		
3968	3978		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB. PAST 10 YEAR TA.

Plugged through: TBG

District: 02

Signed B. J. Hope (TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 23 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3
no
6-9-16

✓