

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00630-00-00
Spot: SWSESE Sec/Twnshp/Rge: 24-30S-8W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: JOE TJADEN Well #: 4-24
County: KINGMAN Total Vertical Depth: 4480 feet

Operator License No.: 34357
Op Name: ATLAS OPERATING LLC
Address: 15603 KUYKENDAHL, STE 200
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4250		
PROD	5.5	4424		250 SX
SURF	9.63	214		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/25/2016 12:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: ZAFAR ULLAH Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK

WitnessType: PARTIAL

Date/Time Plugging Completed: 04/28/2016 4:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

RUN IN HOLE WITH 2 3/8" TUBING TAG BOTTOM AT 4300'. PUMP 35 SX CEMENT, 150 LBS HULLS, 3% CC AT 4300'. TAGGED PLUG AT 3875'. PERFORATE 5 1/2" CASING AT 1200'. PUMPED 35 SX CEMENT, 100 LBS HULLS, 3% CC, 1200'. TAGGED PLUG AT 910'. PERFORATE 5 1/2" CASING AT 800' & 265'. PULL TUBING TO 800', PUMP 50 SX CEMENT 100 LBS HULLS 3% CC. PULL TUBING TO 250'. RUN BACK IN TO TAG. DID NOT TAG PLUG. PUMP ANOTHER 50 SX CEMENT 3% CC PLUG. PULL TUBING TO 250'. PUMP 35 SX CEMENT, CIRCULATE OUT 5 1/2". PULL OUT OF HOLE WITH TUBING. HOOK UP TO 5 1/2" CASING, PUMP 105 SKS CEMENT. CIRCULATE OUT 8 5/8" SURFACE. CUT CASING 4' BGL, CEMENT HAD FELL BACK 30', TOP OFF WITH 10 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4264	4304		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB. PAST 10 YEAR TA.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 23 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

20-9-16