

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-00632-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 24-30S-8W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: JOE TJADEN Well #: 8-24  
County: KINGMAN Total Vertical Depth: 4341 feet

Operator License No.: 34357  
Op Name: ATLAS OPERATING LLC  
Address: 15603 KUYKENDAHL, STE 200  
HOUSTON, TX 77090

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4275		250 SX
SURF	8.63	220		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/21/2016 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ZAFAR ULLAH Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/21/2016 4:00 PM KCC Agent: B. J. HOPE

**Actual Plugging Report:**

RAN IN WITH BAILER AND TAG BOTTOM AT 4015. RUN IN HOLE WITH TUBING TO 4000'. PUMPED 50 SX CEMENT 150 LBS HULLS & 3% CC PLUG. TAGGED PLUG AT 3800'. FOUND RATTY CEMENT IN SURFACE HEAD. RUN BOND LOG (EXCEL) FROM 1200' TO SURFACE. PERFORATE 5 1/2" CASING FOR SQUEEZE HOLES @ 1200, 830 AND 95'. RUN IN HOLE WITH TUBING TO 1200'. PUMP 35 SX CEMENT 3% CC. TAGGED PLUG AT 907'. RUN TUBING TO 806. PUMP 35 SX CEMENT. WITH TUBING AT 250' PUMPED 65 SKS CEMENT CIRCUALTE OUT 5 1/2". HOOK UP 50 5 1/2" CASING PUMP 25 SKS CEMENT PRESSURE UP TO 500#.

**Perfs:**

Top	Bot	Thru	Comments
4275	4341		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB. PAST 10 YEAR TA.

Plugged through: TBG

District: 02

Signed BJ Hope  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

**MAY 23 2016**

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*no*  
*6-9-16*